

INFRASTRUCTURE PLANNING AND FACILITIES PLANNING, DESIGN AND CONSTRUCTION

September 10, 2024

TITLE OF PROJECT: <u>Fee Hall - Renovations to Room C110</u>

PROJECT ISSUE DATE: August 19, 2024

PROJECT NUMBER: CP24012

ADDENDUM NO: 01

GENERAL

This Addendum is issued prior to receipt of Proposals to amend the Contract Documents identified as Fee Hall - Renovations to Room C110,

Except as otherwise specifically mentioned, the general character of the work required by this Addendum shall be the same as originally specified, and all incidentals required in connection with the work hereinafter described shall be included even though not specifically mentioned. When an item is mentioned with additional specifications given, reference shall be made to the original specifications.

Drawing(s) accompanying this Addendum include: N/A

✓ No drawings accompany this Addendum

ITEM NO. **DESCRIPTION** 1 Carpet add alternate. Please price out replacing all existing carpet. If the carpet is replaced, replace it with the same style currently in the suite. A. That would be the Mohawk Group Academic View Carpet in the color Slate. https://www.mohawkgroup.com/products/softsurface/detail/BT433/Academic View?cc=959&cn=Slate&size=2424 Glass Frosting question - To cover the windows in the 2nd Interior Elevation, we would 2 like a frosted gradient 50" - 60" tall. A. Here is an option from 3M: https://www.3m.com/3M/en US/p/dc/v101425000/ Finish on new wood wall - The Acoustic Slat Wood Wall comes prefinished. Please 3 use the 'natural' pre-finish. 4 New interior door finish - Stain new doors to match existing laminate door that is being saved in the Dean's office exiting the corridor. 5 Redoing laminate in Dean's office over the heat registers - Use Wilsonart Misted Zephyr 4843 for laminate to match. A butt joint seam is acceptable if this color matches. If laminate cannot be exactly matched, re-laminate the entire sill in this color. 6 Corridor Mural –. Install new corridor door and sidelights as shown. Patch and prep

adjacent for replacement mural by others.

- Corridor side of filling in the existing doors Where existing corridor walls are infilled, patch terrazzo base to match existing. Provide sample or in place preliminary patch for owner approval.
- Is standard Aluminum storefront acceptable or do we have to do Nxtwall system for new offices Painted hollow metal in SW Pourpoise would be acceptable. Typically, a Nxtwall system would end up being the same cost.
- 9 Need details on partial height frosted vinyl to inside of glass Have the frosted glass vinyl 50"-60" tall. This will allow for more privacy in the office while still allowing to see any visitors.
- Will an air admittance valve be acceptable for the new kitchen sink Yes, this is acceptable to MSU.
- 11 Attachment: Pre-bid walk-thru sign-in sheet from 9/4/2024

End of Addendum



Capital Project Meeting Sign-in Sheet

Project Name: FEE HALL - PENDVATIONS From C110

Capital Project Number: CP24012

Date & Time: 9/4/24 @ 10:00 AML ocation: FEE HALL, C110

Name	Company	Cell Phone	E-mail Address
MATT Kileuis	Nidsen	517-898-7163	MRIGHTUSE NIELSENCONSTRUCT
Tim Sonerville	T.H. Eifert	517 484-9944	tsonerville a theirest com
Carter vandien	Laux Construction	517-525-6343	Estimating@ Laux Construction. ca
Cooper Moore	Moore Trosper	517-202-0486	info@Moole trosper. com
Nick Rodger	Gran Storge	517 281 4623	nivodgers & gunthorpe phunbing. com
Chois Churchill	Johnson o Ward	517 290-4726	chrise e'johnsmucolle.com
		**	
			×