

Yuhasz, Anthony

From: PDC Communication Team <notices@ipf.msu.edu>
Sent: Tuesday, July 14, 2026 1:50 PM
To: Yuhasz, Anthony
Subject: MSU Planning, Design and Construction - Special Construction Standard 321313 Concrete Pavement Update - July, 14 2026

PLANNING, DESIGN AND CONSTRUCTION

INFRASTRUCTURE PLANNING AND FACILITIES

CONSTRUCTION STANDARDS UPDATES

July 14, 2026

Greetings,

There are important updates to Technical Standard [321313 Concrete Pavement](#).

The updates address an industry problem with the Type 1L cement being supplied to our projects, which requires a curing compound to be applied asap to avoid scaling and other surface-related curing issues from occurring.

The updates include, but are not limited to:

- Correction of ASTM designations for cement types (Part 2.1)
- Removal of lin-seal emulsion and addition of ASTM C309, type 2 products (Part 2.11.A)
- Removal of waterproofing compound we specified for within 50' of building entrances (Part 2.11.B)
- Updating of ADA plate product # to be coated instead of the natural finish.

These construction standard updates are designed to help our contractors succeed when installing concrete across all our projects without further problems over the next couple of months.

Please review these updates as soon as possible as they affect construction projects currently underway on campus.

A comprehensive list of design and construction standards is available on the [IPF website](#).

The MSU Planning, Design and Construction Team



MSU Infrastructure Planning and Facilities | 1147 Chestnut Road | East Lansing, MI 48824 US

[Unsubscribe](#) | [Update Profile](#) | [Constant Contact Data Notice](#)